



## PLUTO LNG TRAIN 2

MR Number: 26221-100-MRA-EKLO-00001

Title: Prefabricated Substation Buildings

Scope of Work: The prefabricated substation buildings will house electrical equipment including the following-

- HV switchboards (33kV and/or 6.6kV)
- LV switchboards (690V and 400V)
- AC UPS system
- DC UPS system
- Lighting and power panelboards

Each building will have a separate MCC room, battery room and DCS room. Bidders will be responsible for complete scope including fabrication of the buildings, supply and installation of the equipment, interconnecting cabling/wiring and final acceptance testing (witnessed by Buyer). DCS cabinets shall be free-issued by Buyer for installation and wiring in the substation buildings by Seller.

Compliance with applicable Australian/local regulations, statutory requirements, Australian codes and standards is required.