

## **WORK PACKAGE - FIRE PROTECTION EQUIPMENT SERVICES**

### **LOCATION - CARRAPATEENA MINE SITE**

#### **SERVICES**

##### **General**

- Provide adequate tools, specialised equipment, vehicles and PPE to carry out the services as instructed
- Provide all consumables necessary to perform the maintenance activity
- Fulfil the duties of a "Labour Classification" requested by OZ Minerals and have the appropriate qualifications and competency

##### **Preventive Maintenance**

##### **Minimum Maintenance Requirements**

- Replace faulty equipment as required or provide information to enable planning
- Conduct a fire alarm signal simulation
- Conduct a fire alarm bell and warning deceive operation
- Installation reset back to normal
- Fault find panel issues and resolve
- Report battery condition
- Perform Alarm zone function test
- Complete and file logbook information
- Check Fire pumps starting devices
- Verify pump running pressures
- Record battery voltage
- Check fire pump isolation valves
- Record holding pressures
- Complete a full function test on fire pump sets
- Check pump controller status
- Check pump discharge drains

##### **Critical Spare Parts**

Contractor to identify critical spares necessary to support the recommended preventive maintenance and is expected to hold all identified critical spares either on site or at the Contractor's store (with the ability to supply items within 24hours of request)

##### **Technical Resources**

Contractor to provide experienced personnel and associated technical resources to discuss maintenance issues with the Company Representative

##### **Reporting**

Contractor to provide a report to OZM upon the completion of all work. The report shall include:

- Describe work completed. Condition of equipment and any parts replaced
- Completion of logbooks