

## Tanami Expansion 2 (TE 2) Project - EXPRESSION OF INTEREST (EOI)

**Project Overview:** The Newmont Goldcorp Tanami Operation (NGT) is located in the Tanami Desert of the Northern Territory approximately 530 km north west of Alice Springs. The Brownfields mining operations are located at the Dead Bullock Soak (DBS) area approximately 42 km to the west of the Granites. The nearest settlement is Yuendumu some 250 km southeast of The Granites. The Tanami Expansion 2 (TE 2) Project consists of expanding the mining infrastructure at Newmont Goldcorp Tanami Operations and potential increase of current ore production rate from its current nominal 2.6 Mtpa.

**Package Title:** General Civil Installation

**Package Description:** Civil Works for the following facilities:

Batch plant

- Clear, grub and topsoil strip (where applicable).
- Import, place, compact and trim 100mm of gravel to create pad for batching plant placement.
- Installation of power, comms and water to designated connection point. To include trenching, backfill and tie-in to existing services where applicable.
- Concrete foundations for silo's. Excavate, form, reo and pour. Approx. 50m3 per foundation.
- Concrete apron for batching plant area. 150mm thick, approx. 50m2.
- Minor access roads.

Waste Water Treatment Plant (WWTP)

- Clear, grub and topsoil strip (where applicable).
- Import, place, compact and trim 100mm of gravel to create pad for WWTP placement.
- Concrete slab. Approx. 15m x 10m x 200mm with edge thickening.
- Installation of power and comms to designated connection point. To include trenching (locally), backfill and tie-in to existing services where applicable.
- Assistance with provision of civils for switchover of civils.
- Rehabilitation of previous WWTP site once switchover complete.

EPCM

- Clear, grub and topsoil strip (where applicable).
- Import, place, compact and trim 100mm of gravel to create pad for EPCM office placement.
- Access road and car park construction. Including Import, place, compact and trim to crossfalls 150mm of gravel.
- Installation of power and comms to designated connection point. To include trenching (300m), backfill and tie-in to existing services where applicable.
- Installation of sewer and sewer pump station, including tie-in to existing septic tank.
- Installation and welding of water line including tie-in to existing HDPE water line.
- Minor access roads.

Water Treatment plant

- Clear, grub and strip topsoil
- Cart topsoil to remediation area
- Import, condition, place, compact and trim gravel pad (~100 m x ~65 m)
- Install buried conduit on pad
- Construct bunded concrete slab (Slab will be nominally 200 mm thick, but will also require construction of pedestals, ring beam foundation, sump, etc)
- Construct access road (Only grading is likely to be required – intermittent access)

- Clear pipeline corridor (~200 m x 8 m)

Fridge plant

- Clear, grub and strip topsoil (ammonia plant location and access road)
- Cart topsoil to bioremediation area
- Cut and fill (including condition, compaction and trimming) pad (~120 m x ~60 m) including access road
- Install buried conduit on pad
- Construct bunded concrete slab (Slab will be ~400 mm to 600 mm thick)

Contractors are to supply all labour, equipment and consumables to facilitate the works.

In accordance with Newmont's commitments to building local and Indigenous capacity in the region, the tender evaluation will include a weighting for utilising local regional businesses in the Northern Territory.

Newmont reserve the right to combine this package and or parts of this package with any other project package.

**Key Information to be included in the EOI:**

Must provide a draft Indigenous Relations Management Plan.

Must provide resourcing information specific for the contract package.

Must be able to demonstrate how to meet construction environmental commitments and provide evidence from other projects. Evidence to be supported with key past client reference people and their contact details

Must provide details of a Safety Management system and records of previous safety performance such as LTIFR and RIFR.

Must provide details of a Quality Management system and records of previous performance.

**Key Milestones:**

Tenderers Release Date: 08.06.2020

Target Contract Award Date: 10.07.2020

Completion: 31.10.2020

**Expression of Interest:**

Contractors are invited to express an interest in this package by registering on the ICN Gateway on line platform. Please ensure your ICN company profile is up to date before registering your expression of interest.

**EOI Closing Date:**

05.06.2020

**Contact:**

Industry Capability Network Northern Territory

[www.gateway.icn.org.au](http://www.gateway.icn.org.au).

**Project URL's**

For more information about Newmont please refer to the company website [www.newmont.com](http://www.newmont.com)

**Disclaimer:**

This package description and target award date is indicative only and subject to change. It is intended to provide only a brief outline of certain works that may be required for the TE2 project and should be read in conjunction with the TE2 project description on ICN Gateway.