

Cross River Rail – Tunnels & Stations

Expression of Interest (EOI)

Ceilings & Partitions

General Description

CPB Contractors, BAM, Ghella and UGL Joint Venture (CBGU D&C JV), has been appointed the principal design and construction contractor for the Tunnel and Stations package of the Cross River Rail project, which includes:

- Four new, state-of-the-art underground stations at Boggo Road, Woolloongabba, Albert Street and Roma Street and an upgrade of the Dutton Park station
- A 10.2km rail line from Dutton Park to Bowen Hills, which includes 5.9 kilometres of twin tunnels under the Brisbane River and Brisbane CBD

With major construction expected to be completed in late 2024, Cross River Rail will unlock the bottleneck at the core of Brisbane's transport network, allowing more trains to run more often and integrating with new roads and bus services allowing future network growth in the region.

The project will increase public transport network services, their connectivity and encourage more people to use public transport, helping to ease congestion on major arterial roads.

Cross River Rail will also be one of Queensland's most important job generating projects and will support economic growth and employment for Queenslanders for years to come. During its construction the project will provide an average of 1,500 jobs per year, and create an equivalent of 450 apprenticeships and traineeships throughout the life of the project.

Expressions of Interest

CBGU D&C JV encourages local businesses interested in Ceilings and Partitions to register an expression of interest (EOI) through the ICN Gateway webpage.

Specific Scope Requirements

The Scope of Work may include:

- Suspended aluminium ceiling (approx. 5,000 to 10,000m² qty)
 - o 100mm deep anodised aluminium suspended ceiling finish
 - o Incl. baffle system with acoustic cassette infill
- Waffle ceiling baffles, anodised aluminium frame on 1200 grid with aluminium panel infill (1,000-2,000m² qty)
- Metal cladding flat sheet, anodised aluminium pan suspended ceiling (2,500-3,500m² qty)
- Folded aluminium panels 2mm thick x 2400mm long, 500mm wide, 75mm deep (3,000m² qty)

- Folded aluminium panels 3mm thick, 600mm wide x 1200mm long, spanning between hook-on brackets (2,000m² qty)

Location of works: Brisbane

Forecast Award Date: From October 2021

Delivery Schedule: It is anticipated that these works will be required on site from January 2022

Disclaimer

Scope of Work is indicative only and is intended to be used as a summary description of work which may be required by CBGU D&C JV and may be subject to change. Full scopes of work will be made available to parties that are invited to tender. There is no undertaking to contract or proceed to a competitive process implied by this form. Further contact with interested suppliers will be at CBGU D&C JV's discretion following successful vendor pre-qualification.