

ICN Scope of Work

Package Number	Saunders-007
Package Name	Tank farm bundwall and floor

Scope of Work (SOW)

Construction Contract

- Provision of Bulk Earthworks for:
 - (a) Excavation and bulk fill placement to construct fuel tank storage pad
 - (b) Supporting table drains
- Provision of Final Bund Earthworks and Drainage for:
 - (a) Fuel tank storage pad, consisting of clay liner, crushed rock and select fill
 - (b) Supporting headwall/pit/pipe drainage network and detailed table drain excavation
 - (c) Supporting temporary site drainage to limit erosion and sedimentation
- Provision of concrete bund walls and access ramps
 - (a) Main perimeter bund retaining wall (footing, stem and shear key)
 - (b) Sub-dividing concrete bund walls between the tanks
 - (c) Concrete retaining walls for the earth filled access ramps between the individually banded areas

Minimum SOW Requirements	As per TTP Documentation and Saunders International Standard Contract Conditions
Delivery / Supply Schedule	Proposed delivery July 2022 – July 2023

Registration Information



Saunders International is committed to ensuring Australian Industry the opportunity to participate in US Bulk Fuel Storage Facility.

You are invited to submit an Expression of Interest if you have the relevant capability and capacity to undertake the scope of work. Suppliers and contractors will only be considered for pre-qualification and tender lists if suitably qualified.

All Expressions of Interest (EOIs) are to be completed via ICN Gateway USBulkFuelStorage.icn.org.au.

Please contact ICNNT if EOI assistance is required. Contact details: (08) 8922 9422 or resources@icnnt.org.au

