

Scope of Work for ICN Gateway Scarborough ETL SISC Project

Package Name	Long Reach Excavator_150T
Package Number	WE70/80-SCP-001
Scope of Supply	<ol style="list-style-type: none"> 1. Mobilisation to Dampier, Western Australia 2. Demobilisation from Dampier, Western Australia 3. Wet Hire of machine 12hr and 24hrs 4. Dry hire of machine 12hr and 24hrs 5. Critical spares to be included 6. Hire duration approx. 3 – 4 months Q2 2023 7. There may be a standby period when the pipeline is being installed. We would request a standby rate for this period.
Specifications and Standards:	W1000SG8676422 Lifting Equipment
Minimum Scope of Work Requirements:	<ul style="list-style-type: none"> • The long reach excavator will be required to remove existing armour rock and filter rock from an existing trench. The trench is in an inter-tidal area, the excavator will be always above the water line. • The filter and armour rock will be reinstated following installation of a 36" pipeline within the trench. • Maximum armour rock size is 1,550mm • Minimum reach 23m • Lifting capacity at 16m is minimum 11t • Include specifications of available attachments. • Certified lifting points an advantage, please detail if available
Contact:	<ul style="list-style-type: none"> ▪ Industry Capability Network Western Australia (+61 8) 9365 7623 ▪ Name: Ray Loh <ul style="list-style-type: none"> ○ Phone No.: T: 9365 7499 /M: 0411 768 098 ○ E-mail: Ray.Loh@icnwa.org.au ▪ Please Note: This is a request for specific expressions of interest, vendors and contractors will be considered for prequalification and /or tender if suitably qualified. For general expressions of interest please ensure you are registered with Industry Capability Network Western Australia.
URL	For more information about Boskalis, please refer to the Boskalis website https://www.boskalis.com
Closing Date:	2 May 2021