



PLUTO LNG TRAIN 1: SCARBOROUGH MODIFICATIONS

MR Number: 26457-110-MRA-EKLO-00001

Title: Prefabricated Substations & Plant Buildings

Scope of Work: Furnish all labor, materials, and services for the design, fabrication, testing, preparation for shipment and delivery of prefabricated substation(s) and hazardous area located field auxiliary rooms (FARs).

Substation scope will include LV switchgear and MCC, UPS with associated battery room, Vesda and all building auxiliaries as indicated on drawings, datasheets and material requisition.

Seller shall provide FAR and associated electrical equipment and building auxiliaries as indicated on the drawings and material requisition.

All equipment shall be in accordance with the Technical Specifications and attachments, complete and operational when installed in accordance with Sellers instructions and all other accessories. Seller shall make arrangements for conducting testing of the building(s) which shall be witnessed by a Buyer's representative.